

DRAFT REPORT OF GEOTECHNICAL EXPLORATION PALM COAST VILLAGE PALM COAST, FLORIDA LEGACY PROJECT NO. 22-1041.1

Prepared for:

Mr. Ken Atlee Atlee Development Group 7645 Gate Parkway Suite 202 Jacksonville, Florida 32256

Prepared by:

Legacy Engineering, Inc. 6415 Greenland Road Jacksonville, Florida 32258 Phone: 904.721.1100 www.legacyengineeringinc.com

April 8, 2022



April 8, 2022

Mr. Ken Atlee Atlee Development Group 7645 Gate Parkway Suite 202 Jacksonville, Florida 32256

Draft Report of Geotechnical Exploration and Engineering Services Palm Coast Village Palm Coast, Florida Legacy Project No. 22-1041.1

Dear Mr. Atlee:

As requested, Legacy Engineering, Inc. has completed a portion of geotechnical exploration for the subject project. The exploration was performed to evaluate the general subsurface conditions within the proposed construction areas, and to provide guidelines to facilitate foundation support, earthwork preparation, and paving design.

Due to site access conditions (soft surficial soils and standing water from recent rainfall), portions of the site were not accessible to our ATV-Skidder type drill rig. We will complete the remaining work with our tracked Marooka drill rig once schedule permits. We have prepared this draft report to present the results of the currently completed work and our preliminary recommendations.

We appreciate this opportunity to be of service as your geotechnical consultant on this phase of the project. If you have any questions, or if we may be of any further service, please contact us.

Sincerely: Legacy Engineering, Inc.

Isabella Trejo Geotechnical Specialist Jared Pitts, P.E. Licensed, Florida 92090



Geotechnical & Materials Engineering and Testing

Table of Contents

1.0	PROJECT INFORMATION
1.1 1.2	SITE LOCATION AND DESCRIPTION
2.0	PROJECT DESCRIPTION
3.0	LABORATORY TESTING
4.0	GENERAL SUBSURFACE CONDITIONS
4.1 4.2	GENERAL SOIL PROFILEGROUNDWATER LEVEL
5.0	BUILDING AREA RECOMMENDATIONS
5.1	General
5.2	BUILDING FOUNDATIONS
5.2.1	BEARING PRESSURE
5.2.2	FOUNDATION SIZE
5.2.3	BEARING DEPTH
5.2.4	BEARING MATERIAL
5.2.5	SETTLEMENT ESTIMATES
5.3	SITE PREPARATION FOR SHALLOW FOUNDATIONS
6.0	PAVEMENT RECOMMENDATIONS
6.1	GENERAL
6.2	PAVEMENT SECTION RECOMMENDATIONS
6.3	SITE PREPARATION FOR PAVEMENTS
6.4	ADDITIONAL PAVEMENT CONSIDERATIONS
6.4.1	ASPHALTIC CONCRETE PAVEMENT
6.4.2	GROUNDWATER SEPARATION
7.0	BORROW SUITABILITY
8.0	LIMITATIONS
APPl	ENDIX A
FIELL	O EXPLORATION PLAN
	ERALIZED SOIL PROFILES
	BORING RECORDS
SUMN	MARY OF LABORATORY INDEX TEST DATA
APPl	ENDIX B I
KEYT	O SOIL CLASSIFICATION
	O AND I ARORATORY TEST PROCEDIURES





1.0 PROJECT INFORMATION

1.1 Site Location and Description

The site for the subject project is located on East Moody Boulevard, approximately 0.4 miles west of Seminole Woods Boulevard, in Palm Coast, Florida. The subject site is densely wooded with pine and oak trees, palmettos, and dense underbrush. Adjacent areas to the east, west, and south are occupied by commercial structures. Wetland areas are scattered throughout the site. At the time of our site visit, portions of the wetland areas were inundated with standing water from previous rainfall.

1.2 Project Description

Project information has been provided to us in discussions with you. We were provided with the following documents that show the layout of the proposed construction, property boundary limits, wetland areas, and topographic information:

- Preliminary Site Plan prepared by Baker Design Build
- Site Plan prepared by Sleiman Enterprises
- Wetland Delineation Map dated May 10, 2016, prepared by Carter Environmental Services, Inc.

Based on the information provided to us, we understand the proposed project will consist of constructing a commercial development at the subject site. The construction will consist of commercial structures, parking and drive areas, and a stormwater pond. We have assumed that the construction will include concrete-masonry-units (CMU), timber framing, or preengineered steel framing with exterior steel panels. We have not been provided with detailed foundation loading information; therefore, we have assumed the compressive wall, column, and floor loading will not exceed 4.0 klf, 75.0 kips, and 100 psf, respectively.

Proposed parking and drive areas will likely consist of flexible asphaltic pavement underlain by base course and stabilized subgrade soils. The proposed stormwater pond will be constructed within the southeast portion of the site. We have assumed fill heights for site development will generally not exceed 5 feet above existing grade.

2.0 FIELD EXPLORATION

In order to explore the subsurface conditions within the area of the proposed building areas, 11 Standard Penetration Test (SPT) borings (B1 through B4, B8, B9, B11, and B14 through B17) were performed to a depth of 25 feet each. Within the proposed pavement areas, four auger borings (A3, A4, A5, and A10) were conducted to depths of 3 to 3.5 feet below existing grade. The auger borings were terminated before the scheduled 6-foot exploration depths due to wet subsurface conditions causing the borehole to collapse. The borings were located using a handheld Global Positioning System (GPS) unit, and should be considered accurate to the degree implied by the method utilized. The SPT and auger borings were





conducted in accordance with ASTM D 1586 and ASTM D 1452, respectively. The subsurface conditions encountered at each boring location, and the recorded groundwater levels, are presented on the Generalized Soil Profiles and Test Boring Records in Appendix A.

3.0 LABORATORY TESTING

Soil samples recovered during the field exploration were visually classified in accordance with ASTM D 2488. Additional testing consisting of moisture content and organic content tests were performed to better define the classification of soils encountered and to provide engineering characteristics of the soils. The results of the testing are presented on the Test Boring Records and the Generalized Soil Profiles in Appendix A.

4.0 GENERAL SUBSURFACE CONDITIONS

4.1 General Soil Profile

The boring locations and general subsurface conditions that were encountered are graphically illustrated on the Field Exploration Plan and Generalized Soil Profiles. A relatively detailed description of the encountered subsurface conditions is presented on the Test Boring Records. When reviewing these records, it should be understood the soil conditions may change significantly between the boring locations. The following discussion summarizes the soil conditions encountered.

In general, the borings performed within the area of the proposed structures (B1 through B4, B8, B9, B11, and B14 through B17) encountered very loose to very firm fine sand (SP), fine sand with silt (SP-SM), and fine sand with clay (SP-SC) throughout the 25-foot exploration depths. As an exception, Boring B15 encountered a layer of silty fine sand with many organic materials within the upper 2 feet. Additionally, Borings B2, B9, B16, and B17 encountered layers of silty to very silty fine sand (SM) varying between the depths of 11 and 18.5 feet below existing grade. Topsoil was encountered within the upper 4 to 7 inches.

The auger borings performed within the proposed parking and drive areas (A3, A4, A5, and A10) encountered fine sand (SP) and fine sand with silt (SP-SM) extending to the boring termination depths of 3 to 3.5 feet.

4.2 Groundwater Level

The groundwater level was measured at the boring locations, subsequent to boring completion, at depths varying between the ground surface and 1 foot below existing grade. Based on the results of the soil borings, and review of available published literature, we estimate the seasonal high groundwater level at the groundwater levels measured during this exploration.





5.0 BUILDING AREA RECOMMENDATIONS

5.1 General

The following recommendations are made based upon a review of the attached soil test data, our understanding of the proposed construction, and experience with similar projects and subsurface conditions. If the structural loads, construction locations, or grading information change from those discussed previously, we request the opportunity to review and possibly amend our recommendations with respect to those changes.

Please report to us any conditions encountered during construction that were not observed during the performance of the borings. We will review, and provide additional evaluation as required.

A layer of silty fine sand with many organic materials was encountered at the locations of Boring B15 within the upper 2 feet. A significant portion of this soil type is composed of organic materials which will consolidate under loading information and will therefore result in excessive settlement to the overlying structure. This material should be overexcavated in its entirety from within the building limits.

5.2 Building Foundations

Based on the results of the subsurface exploration, we consider the subsurface conditions at the site favorable for support of the proposed car wash building and pay station when constructed on properly designed shallow foundation systems. Provided the soils are prepared in accordance with the Site Preparation Section of this report, the following parameters may be used for foundation design.

5.2.1 Bearing Pressure

The maximum allowable net soil bearing pressure for shallow foundations should not exceed 3,000 pounds per square foot (psf). Net bearing pressure is defined as the soil bearing pressure at the base of the foundation in excess of the natural overburden pressure. The foundations should be designed based upon the maximum load that could be imposed by all loading conditions.

5.2.2 Foundation Size

The minimum widths recommended for any isolated column footing and continuous wall footings are 24 inches and 18 inches, respectively. Even though the maximum allowable soil bearing pressure may not be achieved, these width recommendations should control the size of the foundations.

5.2.3 Bearing Depth

The exterior foundations should bear at a depth of at least 18 inches below the exterior final grades and the interior footings should bear at a depth of at least 18 inches below the finish





floor elevation to provide confinement to the bearing level soils. We recommend stormwater and surface water be diverted away from the building exteriors, both during and after construction, to reduce the possibility of erosion adjacent to the exterior footings.

5.2.4 Bearing Material

The foundations may bear on either the compacted suitable in-place natural soils or compacted structural fill. The bearing level soils, after compaction, should exhibit densities of at least 95 percent of the maximum dry density as determined by ASTM D 1557 (Modified Proctor), to the depth described subsequently in the Site Preparation section of the report. In addition to compaction, the bearing soils must exhibit stability and be free of "pumping" conditions.

5.2.5 Settlement Estimates

Post-construction settlement of the structure will be influenced by several interrelated factors, such as (1) subsurface stratification and strength/compressibility characteristics of the bearing soils; (2) footing size, bearing level, applied loads, and resulting bearing pressures beneath the foundations; (3) site preparation and earthwork construction techniques used by the contractor, and (4) external factors, including but not limited to vibration from offsite sources and groundwater fluctuations beyond those normally anticipated for the naturally-occurring site and soil conditions which are present.

Our settlement estimates for the structure are based upon the use of successful adherence to the site preparation recommendations presented later in this report. Any deviation from these recommendations could result in an increase in the estimated post-construction settlement of the structure.

Due to the sandy nature of the surficial soils, following the compaction operations, we expect a significant portion of settlement to be elastic in nature. This settlement is expected to occur relatively quickly, upon application of the loads, during and immediately following construction. Using the recommended maximum bearing pressure, the maximum structural loads presented in this report, and the field and laboratory test data which we have correlated to the strength and compressibility characteristics of the subsurface soils, we estimate the total settlements of the structure to be approximately one inch or less.

Differential settlement results from differences in applied bearing pressures and the variations in the compressibility characteristics of the subsurface soils. Based on the subsurface conditions as determined by the borings, it is anticipated that differential settlements will be within tolerable limits.





5.3 Site Preparation for Shallow Foundations

We recommend the following site preparation guidelines for the building areas:

- 1. Implement temporary groundwater control measures, as required. The groundwater should be maintained at least two feet below the depth of excavation required and two feet below compacted surfaces. Temporary groundwater control measures should be the responsibility of the contractor.
- 2. Strip the proposed construction limits of all grass, roots, topsoil and other deleterious materials from within, and extending at least 5 feet beyond, the proposed building limits. Expect initial clearing and grubbing to depths of approximately 6 inches.
 - Over-excavate soil containing significant amounts of organic materials in its entirety, as encountered at the locations of Boring B15. Unsuitable soils should be over-excavated from within, and extending a horizontal distance of at least 5 feet beyond, the proposed building limits.
- 3. Proof-roll the building areas. The proof-rolling should be conducted with a fully-loaded tandem-axle dump truck. The truck should be driven back and forth over the subject area, with each wheel path overlapping the previous in order to provide full site coverage. This will help identify any areas where pumping/yielding soils are present. Any areas that exhibit pumping soils should be addressed by the geotechnical engineer to determine the most effective remedy. Methods typically used to remediate pumping soils are undercutting and replacement, moisture conditioning, etc.
- 4. Compact the exposed surface using a vibratory drum roller having a minimum static, atdrum weight of 7 tons and a drum diameter of at least 5 feet. It is recommended that repeated passes of the roller be made in one direction, followed by repeated passes of the roller in a direction perpendicular to the initial passes. The upper two feet of soils below the exposed surface (after stripping and grubbing) within the building areas should be improved to achieve a minimum compaction requirement of 95% of the Modified Proctor Test (ASTM D 1557). We recommend the soils, at the time of compaction, exhibit moisture contents within 2 percent of the optimum moisture content as determined by the Modified Proctor Test (ASTM D 1557).

The use of the vibratory mechanism on the roller should be used with caution when compacting the exposed surface and the initial lifts of fill in order to avoid drawing the groundwater to the surface and causing soil instability (pumping) conditions. If vibration is drawing water to the exposed surface, the vibratory mechanism should be turned off and the roller should be operated in static mode.





Should the soils experience pumping and soil strength loss during the compaction operations, compaction work should be immediately terminated and (1) the disturbed soils removed and backfilled with dry structural fill soils which are then compacted, or (2) the excess moisture content within the disturbed soils allowed to dissipate before recompacting.

- 5. Test the compacted surface for density at a minimum of one test per 5,000 square feet of building area.
- 6. Place structural fill in loose lifts not exceeding a thickness of 12 inches and compact until finished subgrade is achieved. Structural fill and backfill is typically defined as non-plastic, inorganic, granular soil having less than 10 percent material passing the No. 200 mesh sieve and containing less than 4 percent organic material. Typically, the material should exhibit moisture contents within 2 percent of the Modified Proctor optimum moisture content (ASTM D 1557) during the compaction operations. Compaction should continue until densities of at least 95 percent of the Modified Proctor maximum dry density (ASTM D 1557) have been achieved within each foot of the compacted structural fill.
- 7. Perform density tests within each lift of fill at a minimum of one test per 5,000 square feet of building area.
- 8. Excavate, compact and test footing excavations for density to a depth of one foot below bearing level. We recommend that you test one out of every four column footings and perform one test per every 100 linear feet of wall footing. Compaction operations in confined areas, such as footing excavations, can best be performed with a lightweight vibratory sled or other hand-held compaction equipment.

6.0 PAVEMENT RECOMMENDATIONS

6.1 General

We have assumed the subject project will utilize flexible asphaltic pavement underlain by base course and stabilized subgrade soils. In the following sections, we have presented our recommendations to guide pavement design and site preparation.

6.2 Pavement Section Recommendations

Our recommendations for pavement sections are presented below. Detailed traffic loading conditions were not available; therefore, we have provided pavement sections which can accommodate loading conditions typical of the subject construction over a design life of 20 years. The light duty pavement section is based on 500,000 Equivalent Single Axle Loads (ESALs) of 18 kips. The heavy duty pavement section is based on 1,500,000 ESALs. Frequent use of heavy trucks may warrant a stronger pavement section. Legacy





Engineering can provide a detailed pavement design if provided with the anticipated traffic loading.

Pavement Section	Asphalt ⁽¹⁾ Thickness (in)	Base Course ⁽²⁾ Thickness (in)	Stabilized ⁽³⁾ Subgrade (in)
Light Duty Asphalt	1.5	6.0	12
Heavy Duty Asphalt	2.0	8.0	12

- 1) Flexible pavement should consist of SP 9.5 or SP 12.5.
- 2) Base course should consist of limerock exhibiting an LBR of at least 100, or crushed concrete exhibiting an LBR of at least 130. Limerock and crushed concrete base course materials and gradations should conform to FDOT Standard Specifications for Road and Bridge Construction Sections 911 and 204, respectively.
- 3) Subgrade should exhibit an LBR of at least 40.

6.3 Site Preparation for Pavements

We recommend the following site preparation guidelines for pavement construction:

- 1. Implement temporary groundwater control measures, as required. The groundwater should be maintained at least two feet below the depth of excavation required and two feet below compacted surfaces. Temporary groundwater control measures should be the responsibility of the contractor.
- 2. Strip the proposed construction limits of all grass, roots, topsoil and other deleterious materials from within, and extending at least 3 feet beyond, the proposed pavement limits. Expect initial clearing and grubbing to average depths of approximately 6 inches
- 3. Compact the exposed surface with a vibratory drum roller until densities of at least 95 percent of the modified Proctor maximum dry density (ASTM D 1557) are achieved within the upper one foot below the exposed surface with the exception that densities of at least 98 percent should be obtained in the upper 12 inches below base course. We recommend the compacted soils exhibit moisture contents within 2 percent of the optimum moisture content as determined by the Modified Proctor Test (ASTM D 1557).

Should the soils experience pumping and soil strength loss during the compaction operations, compaction work should be immediately terminated and (1) the disturbed soils removed and backfilled with dry structural fill soils which are then compacted, or (2) the excess moisture content within the disturbed soils allowed to dissipate before recompacting.

Care should be exercised to avoid damaging any nearby structures while the compaction operation is underway. Prior to commencing compaction, occupants of adjacent structures should be notified and the existing conditions of the structures be documented with photographs and survey (if deemed necessary). Compaction should cease if deemed





detrimental to adjacent structures and Legacy Engineering, Inc. should be contacted immediately. It is recommended the vibratory roller remain a minimum of 75 feet from existing structures. Within this zone, use of a vibratory roller operating in the static mode is recommended.

- 4. Test the compacted surface for density at a frequency of not less than one test per 10,000 square feet of pavement area (minimum three locations).
- 5. Place structural fill in loose lifts not exceeding 12 inches and compact until finished subgrade is achieved. Structural fill and backfill is typically defined as non-plastic, inorganic, granular soil having less than 10 percent material passing the No. 200 mesh sieve and containing less than 4 percent organic material. Typically, the material should exhibit moisture contents within 2 percent of the Modified Proctor optimum moisture content (ASTM D 1557) during the compaction operations. Compaction should continue until densities of at least 95 percent of the Modified Proctor maximum dry density (ASTM D 1557) have been achieved within each foot of the compacted structural fill, with the exception that densities of at least 98 percent should be obtained in the upper 12 inches below base course.
- 6. Perform density tests within each lift of fill at a frequency of not less than one test per 10,000 square feet of pavement area (minimum of three locations).
- 7. Place and compact base course until densities of at least 100 percent of the modified Proctor maximum dry density are achieved. Compaction operations should be conducted with the drum roller noted above.
- 8. Perform density tests within the base course at a frequency of not less than one test per 10,000 square feet of pavement area (minimum of three locations).

6.4 Additional Pavement Considerations

6.4.1 Asphaltic Concrete Pavement

Asphaltic concrete mixes should be a current FDOT approved design of the materials actually used. Samples of the materials delivered to the project should be tested to verify that the aggregate gradation and asphalt content satisfies the mix design requirements.

After placement and field compaction, core the wearing surface to evaluate material thickness and to perform laboratory densities. Obtain cores at frequencies of at least one core per 3,000 square feet of placed pavement, or a minimum of two cores per day of production.





6.4.2 Groundwater Separation

Groundwater, if not maintained below the base course an adequate distance, can result in weakened subgrade and base course soils, and therefore a greatly reduced pavement life. It is recommended the seasonal high groundwater level be maintained at least 18 inches below limerock base courses and at least 12 inches below crushed concrete base courses. If the recommended vertical separation cannot be achieved with the proposed finished grades, underdrains can be considered to maintain the groundwater level at the recommended depths.

7.0 BORROW SUITABILITY

Although the borings in the pond area have not yet been performed, it could be anticipated that some suitable fill soils will be present due to the conditions at the remainder of the site.

The fine sand (SP), fine sand with silt (SP-SM), and fine sand with clay (SP-SC), as encountered at the borings, are suitable for use as structural fill and backfill material. The fine sand typically exhibits higher permeability than the fine sand with silt and fine sand with clay, and therefore, is more desirable for use in areas requiring substantial drainage potential. Because the fine sand with silt and fine sand with clay soils inherently retain moisture, strict moisture control will be required to avoid soil instability (pumping) during placement and compaction operations.

Density requirements typical of structural soils are very difficult to achieve with silty and clayey fine sand (SM and SC) due to their extreme nature to retain moisture. Therefore, we do not recommend clayey fine sand (SC) and silty fine sand (SM) for use as structural fill materials.

The soils in the proposed pond area that are below the groundwater level will have moisture contents in excess of the Modified Proctor optimum moisture content and will require stockpiling or spreading to bring the moisture content to within 2 percent of the optimum moisture content corresponding to the required degree of compaction.

8.0 LIMITATIONS

We have conducted the geotechnical engineering in accordance with principles and practices normally accepted in the geotechnical engineering profession. Our analysis and recommendations are dependent on the information provided to us. Legacy Engineering, Inc. is not responsible for independent conclusions or interpretations based on the information presented in this report.




APPENDIX A


FIELD EXPLORATION PLAN


GENERALIZED SOIL PROFILES


TEST BORING RECORDS

SUMMARY OF LABORATORY INDEX TEST DATA









TEST BORING RECORD

JOB NO. 22-1041

В1

03/22/2022

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

Project Palm Coast Village **Boring Location**

See Field Exploration Plan

Ground Elevation N/A **Datum** N/A **Groundwater Depth** 0.5 feet **Casing Size Length of Casing Set** 5 feet 4 inches


Driller DK Engineer Jared Pitts

Boring Completed 03/22/2022

BORING NO.

Boring Begun

Sheet



TEST BORING RECORD

JOB NO. 22-1041

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

BORING NO.

Sheet

STANDARD PENETRATION TEST SYMBOL DEPTH ELEV. MATERIAL DESCRIPTION BLOW COUNT (FT) (FT) BLOWS / 6-INCH - 16 Very Loose Gray Fine SAND with Silt and Trace Shell Fragments (SP-SM), Continued 17 Very Firm to Loose Gray Fine SAND (SP) - 18 - 19 12 23 11 20 -21 22 23 24 8 9 25 Boring Terminated at 25 Feet - 26 27 28 29 30 31

Palm Coast Village

TEST BORING RECORD

JOB NO. 22-1041

of

B2

ENGINEERING, INC.

Ground Elevation

Geotechnical & Materials Engineering and Testing

N/A

Datum

Project Palm Coast Village **Boring Location**

See Field Exploration Plan 0 feet (Ground Surface) N/A **Groundwater Depth**

Boring Begun 03/22/2022 Boring Completed 03/22/2022

BORING NO.

Sheet

Driller DK Engineer Jared Pitts

Casing Size Length of Casing Set 5 feet 4 inches STANDARD PENETRATION TEST SOIL SYMBOL ELEV. DEPTH MATERIAL DESCRIPTION (FT) (FT) BLOWS / 6-INCH COUNT 0 Topsoil (4 inches) Very Loose to Loose Brown Fine SAND with Silt 1 3 and Trace Roots (SP-SM) 2 3 2 3 Loose Brown Fine SAND with Silt (SP-SM) 2 3 10 Firm Gray Brown Fine SAND with Clay (SP-SC) 5 3 16 Firm Light Gray Brown Fine SAND (SP) 4 18 8 9 5 14 10 11 Very Loose Gray Silty Fine SAND with 12 Few Shell Fragments (SM) 13 14 6 2 15 **REMARKS:** BORING & SAMPLING: ASTM D1586/CORE DRILLING: ASTM D2113

TEST BORING RECORD JOB NO. 22-1041

ENGINEERING, INC.

Project

Geotechnical & Materials Engineering and Testing

BORING NO. B2 Sheet ____ 2 ___ of ___ 2

DEPTH (FT) DEPTH (FT) MATERIAL DESCRIPTION DEPTH (FT) DEPTH
Few Shell Fragments (SM), Continued Firm Gray Fine SAND (SP) Firm Gray Fine SAND (SP) 7
- 17
Firm Gray Fine SAND (SP) 7 8 17
Firm Gray Fine SAND (SP) 5 7 8 17
Firm Gray Fine SAND (SP) 5 7 8 17
Loose Gray Fine SAND with Silt (SP-SM)
24
24 — 25 — 25 — 25 — 25 — 25 — 25 — 25 —
Boring Terminated at 25 Feet

Palm Coast Village

TEST BORING RECORD

JOB NO. 22-1041

ВЗ

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

Project Palm Coast Village

Boring Location _ See Field Exploration Plan **Ground Elevation**

N/A Datum N/A Groundwater Depth 0.7 feet Length of Casing Set _____ 5 feet ___ Casing Size _____ 4 inches

of Sheet

BORING NO.

Boring Begun 03/22/2022

Boring Completed 03/22/2022 Driller DK

Engineer Jared Pitts

	- Casing O	ot daing dize + mones					
E1 E1/	DEDTIL		٦, ١	≝ .		STANDARD PENET	RATION TEST
ELEV. (FT)	DEPTH (FT)	MATERIAL DESCRIPTION	SOIL	SAMPLE NO.	ı	BLOWS / 6-INCH	BLOW COUNT
	0	Topsoil (4 inches)	1444			1	
	-	Very Loose Brown Fine SAND with Silt and					
						2	0
		Trace Roots (SP-SM)	1.69361] 1		1	3
	-		E 23 11/12	1			
			trêgêr)î Giraninî	1		2	
	<u> </u>		1.69.001			2	
	F -	V	- (11)				
	<u></u> 3 −	Very Loose to Firm Gray Brown Fine SAND with	61400	2	L	1	3
	ا	Silt (SP-SM)	1.63:01:	1 -		2	3
			((3)())	1			
	L 4 -		61433	lL	L	4	
			1.61.01			5	
	F -		ស្រី មិន និស័និ ស្រែង មាន	1			
	L 5 -		[3	L	8	18
			((1))	١		10	10
	F -		1/4/2/1/1/	1		40	
	⊢ 6 −		1.61	1 L	L	10	
			11111			5	
	-		(4)			7	
	_ 7 _			4	L	′ —	15
	,	Firm to Very Firm Gray Fine SAND with Silt (SP-SM)	0 1 3 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1		8	
	-		VI 11	1		8	
	⊢ 8 −		1.00	1 6	L		
		Very Firm Light Gray Brown Fine SAND (SP)				6	
						9	
	⊢ 9 −			5	_		22
				1 /		13	
				1 /			
	─ 10 ─			1 +	H		
	<u> </u>				H	-	
		Very Loose Gray Fine SAND with Silt (SP-SM)	1.11111	1			
	<u> </u>		6 (a : 10 : 1 : 6 1 : 6 1 :		H	-	
			0 6 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9				
			1,701,773				
	13 —		(H	-	
	L _		6 69 900	1 L			
			1.01100 64400	1		1	
	<u> </u>		11.01:01:0	_	'	1	2
	<u> </u>		664314 664331	6		'	2
				1 1		1	
	<u> </u>		1.63 a.u.	1	T	=	
	<u> </u>		6 C4 3313]			
			10 1 1 1 1 1		<u></u>		
REMARK	(S:	BORING & SAMPL	ING: AST	M D1	586/0	CORE DRILLING: AS	STM D2113

TEST BORING RECORD JOB NO. 22-1041

ENGINEERING, INC.

 BORING NO.
 B3

 Sheet
 2
 of
 2
 Geotechnical & Materials Engineering and Testing Palm Coast Village Project ___

			. 님	щ		STANDARD PENETI	RATION TEST
ELEV. (FT)	DEPTH (FT)	MATERIAL DESCRIPTION	SYMBOL	SAMPLE	Š	BLOWS / 6-INCH	BLOW COUNT
	<u> </u>	Very Loose Gray Fine SAND with Silt	reina:		┢	-	
		(SP-SM), Continued	* 6 4 10 10				
	<u></u> 17 −	Firm Gray Fine SAND (SP)			┞		
	- -						
	<u> </u>				l		
	— 19 —					6	
				7		7	16
	— 20 —				Ц	9	
	— 21 —						
	— 22 —						
	<u> </u>				-		
	<u> </u>	Loose Gray Fine SAND with Silt (SP-SM)	1.01.77			2	
	— 24 —		6 (4 3 3 3 1 1 1 (2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	8	╟	- 2	5
			6 19 3 10 10 10 10 10 10 10 10 10 10 10 10 10	0		3	J
	— 25 —	Boring Terminated at 25 Feet	6 (3 - 1 - 1		H	-	
	<u> </u>	Bonng Tenninated at 25 Teet					
	— 26 —				┞		
	27				┞		
	— 28 —					_	
	— 29 —						
	29 -						
					$\ $		
	<u> </u>						
	<u> </u>				╟		

TEST BORING RECORD

JOB NO.

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing


Project Palm Coast Village **Boring Location**

See Field Exploration Plan 1.0 feet **Groundwater Depth**

Ground Elevation N/A **Datum** N/A **Casing Size Length of Casing Set** 5 feet 4 inches **BORING NO.** В4 Sheet of

Boring Begun 03/22/2022 Boring Completed 03/22/2022

Driller DK Engineer Jared Pitts



TEST BORING RECORD

JOB NO. 22-1041

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

BORING NO.

Sheet

STANDARD PENETRATION TEST DEPTH ELEV. MATERIAL DESCRIPTION (FT) (FT) BLOWS / 6-INCH COUNT - 16 Very Loose to Very Firm Gray Fine SAND with Silt (SP-SM), Continued 17 - 18 8 - 19 7 12 25 13 20 -21 22 · 23 2 24 8 7 25 Boring Terminated at 25 Feet - 26 27 · 28 29 30 - 31 -

Palm Coast Village

TEST BORING RECORD

4 inches

JOB NO. 22-1041

ENGINEERING, INC.

Ground Elevation N/A Datum

Geotechnical & Materials Engineering and Testing

Project Palm Coast Village Boring Location ____

Length of Casing Set _____ 5 feet ____ Casing Size _____

Boring Begun 03/23/2022

BORING NO.

Sheet ____1 of ____

В8

See Field Exploration Plan Groundwater Depth N/A 1 foot (Estimated) Boring Completed 03/23/2022 Driller ____ DK

Engineer _____ Jared Pitts

		Casing Gize Timorios	Т.			RATION TEST
ELEV. (FT)	DEPTH (FT)	MATERIAL DESCRIPTION	SOIL	SAMPLE NO.	BLOWS / 6-INCH	BLOW COUNT
	0	Topsoil (6 inches)	17777		1	
	†	Loose Light Brown Fine SAND with Silt (SP-SM)	F c 4 (11)		2	
	<u></u> 1 −	Loose Light Brown Fine Of 14B with Oil (Of Oil)	¥	1	<u> </u>	5
			F 64 35 13		3 5	
	<u></u>	Loope Light Prown and Dark Cray Prown Mottled			-	
	<u> </u>	Loose Light Brown and Dark Gray Brown Mottled Fine SAND with Silt (SP-SM)	6 (4 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3		6	
	L 3 →	Tille GARD with oilt (of -olw)	(1) (1) (1) (1)	2	_ 4	7
			1,101,111,111,111,111,111,111,111,111,1]	3	•
			1.03201 013343 013343	1	6	
		Firm Gray Fine SAND with Silt (SP-SM)	1,70,70,70,70,70,70,70,70,70,70,70,70,70,		8	
	F 1	,	1.03.00		8	
	<u></u> 5 −		f (3)(1) 1.10 1 (7)	3	<u> </u>	16
			[.] .] .] .] [] .] .]		8	
	⊢ 6 →		1 t 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3		9	
			0-0-0-0-0 0-0-0-0-0-0-0-0-0-0-0-0-0-0-0	6		
	1 _ 1		6 6 9 9 9 9 6 6 9 9 9 9		7	
	$\Gamma' \uparrow$	Firm Gray Brown Fine SAND with Silt (SP-SM)	1.13.14	4	7	14
	† †		t (d d 1) ;]	5	
	- 8 −		(1) (1) (1) (1) (1) (1) (1)		6	
	<u> </u>		6 (64 (64) C (4 (1))	1		
	9 —		1,633013 11131313	5	6	13
			6 63 363 1.01 10 11 6 6 4 31 11	1	7	
	<u></u>		1.63.66 013.00	1 [_	
	'		6 69 903 170 170			
			1.03.00			
			6 63 90 9 1,000 00 9 1,000 00 9		_	
	†	Very Loose Gray Fine SAND with Silt (SP-SM)		1		
	12 —	vory 20000 Cray i ino or true with one (or -olw)	6 64 933	1	<u> </u>	
	F 4					
	<u>13</u>		F F # 3 1 1 1		L _	
			1016 3 of 40 10 t 3 (1.4)			
			146146 111499	1	1	
			(6	1	3
			# 60 0 41 1 - 64 - 64 1 6 (4 4 1 0 1		2	
	15 —		14136	!	 	
	F -		(
REMARK	I L (S:	BORING & SAMP	เมลาน: LING: AST	M D15	 586/CORE DRILLING: A	STM D2113

TEST BORING RECORD JOB NO. 22-1041

ENGINEERING, INC.

 BORING NO.
 B8

 Sheet
 2
 of
 2
 Geotechnical & Materials Engineering and Testing Palm Coast Village Project ___

			٦.	щ	Ţ	STANDARD PENET	RATION TEST
ELEV. (FT)	DEPTH (FT)	MATERIAL DESCRIPTION	SOIL SYMBOL	SAMPLE	2	BLOWS / 6-INCH	BLOW COUNT
	<u></u> 16 −	Very Loose Gray Fine SAND with Silt	00000000000000000000000000000000000000				
	_	(SP-SM), Continued	i tanini Lijiri				
	<u> </u>		1.63 (0.66) 4 6 3 (0.46) 6 6 3 (0.66) 1.76 (0.77)			-	
	_		6699999 6699999				
	<u> </u>		1.00 (0.00)				
	-					3	
	19 —			7		2	3
	_ 20 —		7 463 36 63 6 7 4 4 3 13 6 63 36 13			1	
	<u> </u>						
	_ 22 _		1,101,107,10 6		L	. <u> </u>	
			000000000 00000000 10000000				
	<u> </u>		6 (4 4 1 1 1 1 7 (5 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			. <u> </u>	
	-		669999 1000000 1000000 1000000 1000000 1000000			2	
	<u> </u>		rajari Kalani	8	I	1 -	2
	-					1	-
	<u> </u>	Boring Terminated at 25 Feet	1433513				
	_						
	<u> </u>					· _	
	<u> </u>					_	
	28						
						-	
	<u> </u>					_	
	<u> </u>						
	30 —						
	-						
	<u> </u>				ig		
					Ш		

TEST BORING RECORD

JOB NO.

of

В9

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

Project Palm Coast Village See Field Exploration Plan **Boring Location**

0.5 feet **Ground Elevation** N/A **Datum** N/A **Groundwater Depth**

Boring Begun


BORING NO.

Sheet

03/23/2022 Boring Completed 03/23/2022

Driller DK

Casing Size Length of Casing Set 5 feet 4 inches Engineer Jared Pitts



TEST BORING RECORD JOB NO. 22-1041

ENGINEERING, INC.

BORING NO. B9 Geotechnical & Materials Engineering and Testing Sheet 2 of Palm Coast Village **Project**

Project	Faim Coast Village		— '	Sileet2	ע
ELEV BERTU		۵,	ш	STANDARD PENET	RATION TEST
ELEV. DEPTH (FT)	MATERIAL DESCRIPTION	SYMBOL	SAMPLE NO.	BLOWS / 6-INCH	BLOW COUNT
- 16	Very Loose Dark Gray Very Silty Fine SAND (SM), Continued Loose Gray Fine SAND with Silt (SP-SM)		7	4 4 4	8
23 24 25 26 	Boring Terminated at 25 Feet	66306 64306 94306 64306 64306 64306 94306 94306 94306 94306 94306	8	3 - 4 3 - —	7
27 28 29 30 31				 	

TEST BORING RECORD

0.5 feet

JOB NO. 22-1041

B11

ENGINEERING, INC.

Ground Elevation

Geotechnical & Materials Engineering and Testing

N/A

Datum

Project Palm Coast Village **Boring Location** See Field Exploration Plan

N/A


Groundwater Depth

Sheet of **Boring Begun** 03/23/2022

BORING NO.

Boring Completed 03/23/2022 Driller DK

Engineer Jared Pitts



TEST BORING RECORD

JOB NO. 22-1041

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

BORING NO.

Sheet

STANDARD PENETRATION TEST DEPTH ELEV. MATERIAL DESCRIPTION (FT) (FT) BLOWS / 6-INCH COUNT - 16 Very Loose to Loose Gray Fine SAND with Silt (SP-SM), Continued 17 - 18 3 - 19 2 3 20 -21 22 · 23 24 8 6 25 Boring Terminated at 25 Feet - 26 27 · 28 29 30 - 31

Palm Coast Village

TEST BORING RECORD

0.3 feet

JOB NO.

B14

ENGINEERING, INC.

Ground Elevation

Geotechnical & Materials Engineering and Testing

N/A

Datum

Project Palm Coast Village **Boring Location** See Field Exploration Plan

Groundwater Depth

N/A

Sheet of 03/23/2022 Boring Begun

BORING NO.

Boring Completed 03/23/2022 Driller DK

LEV.	DEPTH		ᄀᅼᅜ	뿔 .	STAN	DARD PENET	
FT)	(FT)	MATERIAL DESCRIPTION	SOIL SYMBOL	SAMPLE NO.	BLOW	'S / 6-INCH	BLOW COUNT
	0	Topsoil (5 inches)	1444			2	
	├	Very Loose to Loose Gray and Dark Brown Silty Fine	(t a :1:1:			,	
	L 1 →	SAND with Some Organic Materials and		1	_	' _	4
		Trace Roots	i de la como			3	
		Trace Noots				2	
	<u></u>	Moisture Content = 40.1%		-	-		
			r (3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3			2	
		Organic Content = 4.7%				2	
	<u></u> ∃ 3 →	Loose to Firm Gray Brown Fine SAND with Silt	1.01.00	2	_	3	5
	⊢ ⊢	and Trace Roots (SP-SM)	6 t a 2101 1 6 1 3 1 1 1	ı			
	\perp $_{4}$ \perp				L	3	
			terenerali Generalis			5	
	├ <u></u>	Firm Light Gray Brown Fine SAND (SP)				8	
	<u></u> 5 →	Fill Light Gray blown Fille SAND (SF)		3	_	° —	18
						10	
						11	
	<u></u> 6 →			6	\vdash		
						7	
						7	
	<u></u>	Firm Gray Fine SAND with Silt (SP-SM)		4		7	14
	├ -	Thin Gray Thio or and Man One (or Givi)	reina: Eleidie				
	L 8 →			L	L	5	
		Loose Gray Brown Fine SAND with Silt (SP-SM)				5	
	├ <u> </u>		1 13 13			5	
	 9			5	-	-	10
			664999 14939919			5	
			[[]]]]]]]				
	<u>├</u> 10 ┤			r	T		
	├ -						
	L 11 —		iorional Principal		L		
	'']		# 63 (1911) 4 (64 (194) 5 (84 (195))				
		Very Loose to Firm Gray Fine SAND with					
	<u> </u>	Silt (SP-SM)			F	-	
	L J	One (OI -OIVI)	6 f a a úir 1 6 g a a c				
	<u></u> 13 →		1.1(1:1:1)		 		
	├ -		6 (4 0 0 0) 1 (5 (1)				
	L 11 _		663000 66300			2	
				6	_	2	3
	├ <u> </u>		111111			1	
	<u> </u>				Ļ	' _	
	Γ \dashv		111111				

TEST BORING RECORD

JOB NO. 22-1041

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

BORING NO.

Sheet

STANDARD PENETRATION TEST DEPTH ELEV. MATERIAL DESCRIPTION (FT) (FT) BLOWS / 6-INCH COUNT - 16 Very Loose to Firm Gray Fine SAND with Silt (SP-SM), Continued 17 - 18 - 19 7 10 20 -21 22 · 23 6 24 8 6 12 25 Boring Terminated at 25 Feet - 26 27 · 28 29 30 - 31 -

Palm Coast Village

TEST BORING RECORD

4 inches

1.0 feet

JOB NO. 22-1041

B15

ENGINEERING, INC.

Ground Elevation

Geotechnical & Materials Engineering and Testing

N/A

Datum

Length of Casing Set _____ 5 feet ___ Casing Size _____

Project Palm Coast Village Boring Location _ See Field Exploration Plan

Groundwater Depth

N/A

of Sheet 03/23/2022 Boring Begun

BORING NO.

Boring Completed 03/23/2022 Driller DK

Engineer Jared Pitts

ST/	A N ID A D D D D D D D D D D D D D D D D D	
ELEV. DEPTH MATERIAL DESCRIPTION 불요[군승	ANDARD PENET	RATION TEST
(FT) (FT) WATERIAL DESCRIPTION SEE BLC	OWS / 6-INCH	BLOW COUNT
Topsoil (7 inches)	1	
Vory Loogo Dark Brown Silty Fine SAND with Many	1	
Very Loose Dark Brown Silty Fine SAND with Many	_	3
Organic Materials and Trace Roots	2	
Moisture Content = 40.9%	2	
Organic Content = 9.0%	2	
Loose to Firm Light Brown Fine SAND (SP)	3	
	3	6
	3 —	
	2	
Firm Gray Brown Fine SAND (SP)	5	
	12	17
	14	
	9	
Firm Light Gray Brown Fine SAND (SP)	9	40
	7	16
	7	
	_	
	7	
	9	18
	9	10
	_	
Very Loose to Firm Gray Fine SAND with		
Silt (SP-SM)		
— 14 — — — — — — — — — — — — — — — — — —	1	
	2	3
(1	
15	_	
REMARKS: BORING & SAMPLING: ASTM D1586/COF	RE DRILLING: A	STM D2113

TEST BORING RECORD JOB NO. 22-1041

ENGINEERING, INC.

 BORING NO.
 B15

 Sheet
 2
 of
 2
 Geotechnical & Materials Engineering and Testing Palm Coast Village Project ___

1 10,000 _		Tann Oddst Village		_	<u> </u>	. "
			Ţ	ш	STANDARD PENE	TRATION TEST
ELEV. (FT)	DEPTH (FT)	MATERIAL DESCRIPTION	SOIL SYMBOL	SAMPLE NO.	BLOWS / 6-INCH	BLOW COUNT
	- 16			7		10

TEST BORING RECORD

JOB NO. 22-1041

of

Boring Completed 03/23/2022

B16

03/23/2022

ENGINEERING, INC.

Ground Elevation

Length of Casing Set

Geotechnical & Materials Engineering and Testing

N/A

Datum

5 feet

Project Palm Coast Village **Boring Location** See Field Exploration Plan

Casing Size

1.0 feet N/A **Groundwater Depth**

4 inches

Driller DK Engineer Jared Pitts

Sheet

BORING NO.

Boring Begun

STANDARD PENETRATION TEST SOIL SYMBOL ELEV. DEPTH MATERIAL DESCRIPTION (FT) (FT) BLOWS / 6-INCH COUNT 0 Topsoil (6 inches) Very Loose to Loose Gray Fine SAND (SP) 2 1 3 2 2 2 Loose to Firm Brown Fine SAND with Silt (SP-SM) 2 3 6 3 17 Firm Light Brown Fine SAND with Silt and Trace 9 Clay (SP-SM) 13 6 10 Firm Light Brown and Brown Mottled Fine SAND (SP) 10 4 20 10 8 Firm Light Gray Brown Fine SAND (SP) 5 5 9 11 10 · 11 Very Loose Gray Silty Fine SAND (SM) 12 13 14 6 2 15 **REMARKS:** BORING & SAMPLING: ASTM D1586/CORE DRILLING: ASTM D2113

TEST BORING RECORD JOB NO. 22-1041

ENGINEERING, INC.

BORING NO. B16 Geotechnical & Materials Engineering and Testing Sheet 2 of Palm Coast Village **Project**

Project _		Faim Coast Village		_	Sileet	01
ELEV.	DEPTH	MATERIAL DESCRIPTION	SOIL	SAMPLE	STANDARD PENE	BLOW
(FT)	(FT)		l s ₹	81	BLOWS / 6-INCH	COUNT
	- 16 - - 17	Very Loose Gray Silty Fine SAND (SM), Continued				
	- 18 - - 19	Loose to Firm Gray Fine SAND with Silt (SP-SM)	6.3373 F.63.351 V.63.351		1	
	20		6 6 3 6 3 6 3 6 6 6 6 6 6 6 6 6 6 6 6 6	7	5	8
	— 21 — –		1.63 90 to 1.63 90 to 1.63 90 to 1.63 90 to 1.63 90 to			
	_ 23 _		6 63 666 1000 1000 6 63 666 6 63 666 6 63 666 1000 100 1000 100 6 63 666 6 63 666 8 63 666			
	24 25		P. 19 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	8	7 6 7	13
		Boring Terminated at 25 Feet				
	27				_	
	- 28 - - 29 -					
	— 30 — — –					
	— 31 —				-	

TEST BORING RECORD

JOB NO. 22-1041

of

Boring Completed 03/23/2022

B17

03/23/2022

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

Project Palm Coast Village **Boring Location** See Field Exploration Plan

0 feet (Ground Surface) **Groundwater Depth**


Ground Elevation N/A **Datum** N/A Length of Casing Set 5 feet **Casing Size** 4 inches

Driller DK Engineer Jared Pitts

BORING NO.

Boring Begun

Sheet



TEST BORING RECORD

JOB NO. 22-1041


ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing

BORING NO.

B17

Sheet Palm Coast Village




TEST BORING RECORD

JOB NO.

ENGINEERING, INC. **BORING NO.** А3 Geotechnical & Materials Engineering and Testing Sheet of Project Palm Coast Village **Boring Begun** 02/14/2022 See Field Exploration Plan **Boring Location** Boring Completed 02/14/2022

N/A N/A 0.2 feet **Ground Elevation** Datum **Groundwater Depth** Driller DK Length of Casing Set N/A **Casing Size** N/A Engineer Jared Pitts



TEST BORING RECORD

JOB NO. 22-1041

ENGINEERING, INC.

Geotechnical & Materials Engineering and Testing Project

Palm Coast Village Boring Location _____ See Field Exploration Plan Ground Elevation N/A Datum N/A Groundwater Depth 0.3 feet BORING NO. Sheet 1 of 02/14/2022 Boring Begun

Boring Completed 02/14/2022 Driller ____ DK

	f Casing Set	N/A Casing Size N/A N/A	0.5 leet		_	Engineer		ed Pitts
				.ਰ	щ	STANDA	RD PENETR	ATION TEST
ELEV. (FT)	DEPTH (FT)	MATERIAL DESCRIPTION	ē	SYMBOL	SAMPI	BLOWS	/ 6-INCH	BLOW COUNT
	0 -	Topsoil (8 inches)	¥,7	777. 777. 777.				
	1 -	Light Brown Fine SAND with Silt and Tra Roots (SP-SM)	[.] 1.1	rý statal Bá 920 B Ca a stat Bá a stat Bý ac tal	1			
	_ 2	Light Brown Fine SAND with Silt (SP-SN	fi			_	_	
	_ 3 _	· ·	្រី () ស្រី () ស្រី ()		2	Ĺ		
	L		[: 1] .					
	— 4 —	Boring Terminated at 3.5 Feet Due to Bore Collapse	hole			L	_	
	<u> </u>	·						
	5 —							
	6 —					-		
	7 -					L		
	8 -							
	— 9 —					_	_	
	- 10 -							
	11					_		
	<u> </u>					_	_	
	13 —							
	<u> </u>							
	15					_		
EMARK	S:	BORIN	IG & SAMPLING:	: ASTN	// D1	586/CORE D	RILLING: AS	TM D2113

TEST BORING RECORD

JOB NO. 22-1041

ENGINEERING, INC. BORING NO. Α5 of Sheet Geotechnical & Materials Engineering and Testing 02/14/2022 Project Palm Coast Village Boring Begun Boring Location _ See Field Exploration Plan Boring Completed 02/14/2022 Driller ____ Ground Elevation N/A Datum N/A **Groundwater Depth** 0 feet (Ground Surface) DK

Length of	f Casing Set _	N/A Casing Size	N/A		_ [Engineer	Jared Pitts
ELEV.	DEPTH			, Z	를. -	STANDARD PE	NETRATION TEST
(FT)	(FT)	MATERIAL DESCRIPTION		SOIL SYMBOL	SAMF NO	BLOWS / 6-INC	H BLOW COUNT
	0	Topsoil (6 inches	<u> </u>				
		Gray Brown Fine SAND with	Silt (SP-SM)	1.01.01.0			
		,	,	6.630000 6.6300000	1	_	
	F 1			1.00000			
	<u></u>	Light Gray Brown Fine S	AND (SD)	1-1-1-1-1		_	_
	<u> </u>	Light Gray Brown i line G	(OI)				
	<u></u> з —				2	_	_
	<u> </u>	D : T : () () () ()					
	L 4 -	Boring Terminated at 3.5 Feet [Collapse	Due to Borenole			_	
		Collapse					
	_ 5 _						
	6						
						_	
	8 -					_	\neg
	F -						
	 9 					_	\dashv
	10 —					_	_
	F 4						
	11					_	
	<u> </u>						
	<u>12</u>					_	
	<u> </u>					_	
	14						
	T . 1						
	15 —					_	
REMARK	S:		BORING & SAMPLI	NG: AST	M D15	86/CORE DRILLIN	G: ASTM D2113

TEST BORING RECORD

JOB NO.

ENGINEERING, INC. **BORING NO.** A10 Geotechnical & Materials Engineering and Testing Sheet of Project Palm Coast Village Boring Begun 02/14/2022 **Boring Location** See Field Exploration Plan Boring Completed <u>02/14/2022</u> N/A 0.3 feet **Ground Elevation** Datum N/A **Groundwater Depth** Driller DK

Length of Casing Set N/A **Casing Size** N/A Engineer Jared Pitts STANDARD PENETRATION TEST SOIL SYMBOL ELEV. DEPTH MATERIAL DESCRIPTION (FT) (FT) BLOWS / 6-INCH COUNT 0 Topsoil (6 inches) Dark Gray Brown Fine SAND with Silt (SP-SM) 1.63:01 643:03 643:03 Light Brown Fine SAND (SP) 2 3 Boring Terminated at 3.5 Feet Due to Borehole Collapse 5 10 11 12 13 14 15

REMARKS:

BORING & SAMPLING: ASTM D1586/CORE DRILLING: ASTM D2113



Geotechnical & Materials Engineering and Testing

LEGACY ENGINEERING, INC 6415 GREENLAND ROAD JACKSONVILLE, FL 32258

904-721-1100 OFFICE 904-722-1100 FAX

SUMMARY OF LABORATORY INDEX TEST RESULTS

Palm Coast Village
Palm Coast, Florida
Legacy Engineering Project No. 22-1041.1

Standard Sieve Liquid Plastic Plasticity Moisture Organic Unified Soil Limit Limit Index Content Classification	#60 #100 #200	4.7% SP-SM	- 40.9% 9.0%	
iquid Plastic				
Percent Passing U.S. Standard Sieve ¹ Li				
Depth Range, Feet	From To	0.4 2	0.6 2	
Sample No.		1	1	
Boring No		B14	B15	

Notes: 1. Grain size distribution testing performed in accordance with ASTM D422. Fines content testing performed in accordance with ASTM D1140

2. Performed in accordance with ASTM D4318

3. Performed in accordance with ASTM D2216

4. Performed in accordance with ASTM D2974



APPENDIX B

KEY TO SOIL CLASSIFICATION
FIELD AND LABORATORY TEST PROCEDURES



KEY TO SOIL CLASSIFICATION

CORRELATION OF PENETRATION WITH RELATIVE DENSITY & CONSISTENCY

SANDS AND GRAVEL				
BLOW COUNT	RELATIVE DENSITY			
0-4	VERY LOOSE			
5-10	LOOSE			
11-20	FIRM			
21-30	VERY FIRM			
31-50	DENSE			
OVER 50	VERY DENSE			

SILTS AND CLAYS				
BLOW COUNT	CONSISTENCY			
0-2	VERY SOFT			
3-4	SOFT			
5-8	FIRM			
9-15	STIFF			
16-30	VERY STIFF			
31-50	HARD			
OVER 50	VERY HARD			

PARTICLE SIZE IDENTIFICATION (UNIFIED CLASSIFICATION SYSTEM)

CATEGORY	DIMENSIONS		
Boulders	Diameter exceeds 12 inches		
Cobbles	3 to 12 inches		
Gravel	Coarse – 0.75 to 3 inches in diameter Fine – 4.76 mm to 0.75 inch diameter		
Sand	Coarse – 2.0 mm to 4.76 mm diameter Medium – 0.42 mm to 2.0 mm diameter Fine – 0.074 mm to 0.42 mm diameter		
Silt and Clay	Less than 0.074 mm (invisible to the naked eye)		

MODIFIERS

These modifiers provide our estimate of the amount of minor constituent (sand, silt, or clay size particles) in the soil sample

PERCENTAGE OF MINOR CONSTITUENT	MODIFIERS
0% to 5%	No Modifier
5 % to 12 %	With Silt, With Clay
12% to 30%	Silty, Clayey, Sandy
30% to 50%	Very Silty, Very Clayey, Very Sandy

APPROXIMATE CONTENT OF OTHER COMPONENTS (SHELL, GRAVEL, ETC.)	MODIFIERS	APPROXIMATE CONTENT OF ORGANIC COMPONENTS
0% to 5%	TRACE	1 to 2%
5% to 12%	FEW	2% to 4%
12% to 30%	SOME	4% to 8%
30% to 50%	MANY	>8%

FIELD AND LABORATORY TEST PROCEDURES

Penetration Borings

The penetration borings were made in general accordance with ASTM D 1586-67, "Penetration Test and Split-Barrel Sampling of Soils". Each boring was advanced to the water table by augering and, after encountering the groundwater table, further advanced with a rotary drilling technique that uses a circulating bentonite fluid for borehole flushing and stability. At two-foot intervals within the upper 10 feet and at five-foot intervals thereafter, the drilling tools were removed from the borehole and a split-barrel sampler inserted to the borehole bottom. The sampler was then driven 18 inches into the material using a 140-pound SPT hammer falling, on the average, 30 inches per hammer blow. The number of hammer blows for the final 12 inches of penetration is termed the "penetration resistance, blow count, or N-value". This value is an index to several in-place geotechnical properties of the material tested, such as relative density and Young's Modulus.

After driving the sampler 18 inches (or less, if in hard rock or rock-like material) at each test interval, the sampler was retrieved from the borehole and a representative sample of the material within the split-barrel was placed in a watertight container and sealed. After completing the drilling operations, the samples for each boring were transported to our laboratory where our Geotechnical Engineer examined them in order to verify the driller's field classifications. The samples will be kept in our laboratory for a period of two months after submittal of formal written report, unless otherwise directed by the Client.

Auger Borings

The auger borings were performed using a continuous flight auger attached to a rotary drill rig or manually using a post-hole auger; and thus in general accordance with ASTM D 1452-80, "Soil Investigation and Sampling by Auger Borings". Representative samples of the soils brought to the ground surface by the augering process were placed in watertight containers and sealed. After completing the drilling operations, the samples for each boring were transported to the laboratory where the Geotechnical Engineer examined them in order to verify the driller's field classifications. The samples will be kept in our laboratory for a period of two months after submittal of formal written report, unless otherwise directed by the Client.

Soil Classification

Soil samples obtained from the performance of the borings were transported to our laboratory for observation and review. An engineer, registered in the State of Florida and familiar with local geological conditions, conducted the review and classified the soils in accordance with ASTM 2488. The results of the soil classification are presented on the boring records.

Moisture Content

The moisture content of the sample tested was determined in general accordance with ASTM D 2216. The moisture content is the actual moisture content of the sample as sampled in the field during the performance of the soil boring.

Organics Content

The organics content of the sample tested was determined in general accordance with ASTM D 2974. The organics content is the percent of loss of material of an oven-dried sample of material after the sample has been heated in a muffle furnace to 440 °C.